

Buildings Construction Procurement StrategyUpdate Q4 2023

Disclaimer:

This presentation is provided for information only and cannot be considered as binding Ref. F4E_D_2ABES6 v5.1



Table of Contents



1. Overview of the ITER Buildings

2. Packaging Strategy

3. Overview of the Procurement Packages


4. Status of ongoing procurements

5. Upcoming Procurements

1. Overview of ITER Buildings



ITER Buildings Layout



2. Packaging Strategy



Procurement of Large Packages: Schedule – driven by need dates

Preliminary Works



Foundation Tokamak & Site Adaptation Works

Ongoing Works




Neutral Beam Power and Fast Discharge (34, 37,75) and Control building (71); Long Lead - Mechanical Handling, Main Civil & Finishing, Main M&E/Services, Retrofit and Finishing Works; Emergency Electrical Power Distribution, Site Infrastructure Works (partial relaunch of TB08); Painting and Coating for the Tokamak Complex, Tokamak Complex Doors Completion, Electrical and mechanical works for the Tokamak Complex and surrounding buildings; Civil, Architectural, Finishing and Retrofitting works on existing buildings and infrastructures and some related engineering activities, Completion of Tritium Building (14), Emergency distribution buildings (44-47), Heavy Nuclear and Confinement Doors; Provision of Engineering and Construction Consultancy Services

Upcoming Works

Architect Engineer Services II (post 2025); Miscellaneous Infrastructure, Mechanical, Electrical and Instrumentation & Control, Finishing and Retrofit Works in Non-Nuclear Buildings and Infrastructure; Emergency power distribution system - supply and installation of IP Electrical Diesel Generators; Building 14 services post First Plasma; Electrical Diesel Generators, Fuel Tanks and buildings 42, 43, 57-60; Definition of new ground spectrum HCF; Hot Cell complex (21,23,24) HCC Civil Works / HCC Buildings Services/ HCC mechanical works (HCC doors, liner, lifting means); Hot Cell Complex Architect Engineer/Engineering support for Design activities.

3. Overview of the Procurement Packages - Layout





3. Overview of the Procurement Packages - Completed/Ongoing Contracts



	TB00	F4E-OPE-095	Construction of the TC Seismic Isolation Pit, Supply and Installation of Anti-Seismic
			Bearings
	TB01	F4E-OPE-251	Site Adaptation
Completed	TBAlpha	F4E-OPE-406	Galleries and drainage works
	TB05	F4E-OPE-378	D&B Package
	TB06	F4E-OPE-428	HV Electrical Equipment
	TB07	F4E-OPE-429	D&B Package
	TB03	F4E-OPE-286	Main Civil & Finishing
Terminated	TB08	F4E-OPE-374	Site Infrastructure Works
Terrilliated			
	TB02	F4E-OPE-285	Long Lead - Mechanical Handling
	TB04	F4E-OPE-301	Main M&E/Services
	TB11	F4E-OFC-755	Retrofit and Finishing Works
	TB12	F4E-OPE-688	Design and Build Buildings 34, 37, 75 and 71
	TB13	F4E-OPE-1003	Emergency Electrical Power Distribution 44-47
Ongoing	TB16	F4E-OPE-636	Site Infrastructure Works (partial relaunch of TB08)
Origonia	TB18	F4E-OPE-996	Completion of the Tritium Building 14
	TB19	F4E-OPE-906	Painting and Coating for the Tokamak Complex
	TB20	F4E-OPE-1099	Tokamak Complex Doors Completion
	TB21	F4E-OMF-1107	Electrical and mechanical works for the Tokamak Complex and surrounding buildings
	TB22 Lot B	F4E-OMF-1168	Civil, Architectural, Finishing and Retrofitting works

4. Status of ongoing procurements



Ongoing procurements

F4E-OMF-1168 TB22

Lot A - Civil, Architectural, Finishing and Retrofitting works

Lot D - Primary Structural works

TB22 – F4E-OMF-1168 Civil, Architectural, Finishing and Retrofitting works



Procurement Process: Competitive Procedure with Negotiation

Contract Type: FIDIC

Key Dates:



	LOT A	LOT C	LOT D	LOT E
Issue of Pre Information Notice	Q2-2021		Q2-2021	
Issue of Invitation to Participate (step 1)	Q3-2021	Cancelled.	Q3-2021	
Issue of Call For Tender (step 2)	Q2-2022	To be relaunched as	Q2-2023	Cancelled
Receipt of Tenders	Q4-2022	TB 25 (Slide 11)	Q4-2023	
Contract Award	Q4-2023		Q2-2024	
Contract Signature	Q4-2023		Q2-2024	

AE II – Architect Engineer Services (post 2025)



Procurement Process: Competitive Procedure with Negotiation

Contract Type: Direct contract



Key Dates:

Issue of Pre Information Notice	Q1-2023
Issue of Invitation to Participate (step 1)	Q3-2023
Issue of Call For Tender (step 2)	Q4-2023
Receipt of Tenders	Q1-2024
Contract Award	Q3-2024
Contract Signature	Q3-2024

5. Upcoming Procurement Packages



TB25	Miscellaneous infrastructure, mechanical, electrical and instrumentation & control, finishing and retrofit works
TB24	IP Electrical Diesel Generators and buildings 59, 60
TB23	Building 14 services post First Plasma
TB17	PIC Electrical Diesel Generators, Fuel Tanks and buildings 42, 43, 57, 58
Service Contract	Legal inspection
Service Contract	Definition of new ground spectrum HCF
Hot Cell Complex	Construction of Hot Cell (21), Radwaste (23) Personal Access Control Building (24) & Control Building (71) PIC Engineering support for Civil Works and Buildings services

TB25 – Miscellaneous infrastructure, mechanical, electrical and instrumentation & control, finishing and retrofit works



Scope:

Geotechnical Investigations, Topographic survey, Earthworks; Infrastructures works (outside buildings); Equipment fences and protection, landscaping, parking, road and surfacing, paving, etc.; Integrated Plant Earthing Grid (IPEG) installation and connection with Qualifoudre certification; Piping works, gas or fluid networks (e.g. PBS65 Liquid and gas networks, PBS26 cooling water system); Site Networks with all associated equipment (valves, SDP, manholes, chambers, covers etc.); Simple Special foundation and slabs; Concrete structures demolition; Dewatering, soil treatment; Doors, gates, portals; False Ceiling; Partitioning; Floor finishing (e.g. Tilling); End-user Plumbing, Toilets accessories; Signage, tagging; Windows; Building and tunnels (galleries) services; Operation & maintenance of works done by The Contractor or by Others - [Option]; Miscellaneous services (general logistics) - [Option]; Coating and painting, and painting touch-ups including after support installation - [Option].



Koy Datos

Estimated value / volume: <20M€

Estimated launch: Q4 2023

Procurement Process: Competitive Procedure with Negotiation

Contract Type: Supply

	Rey Dates.
Issue of Pre Information Notice	Q1-2023

Issue of Pre Information Notice	Q1-2023
Issue of Invitation to Participate (step 1)	Q4-2023
Issue of Call For Tender (step 2)	Q1-2024
Receipt of Tenders	Q1-2024
Contract Award	Q3-2024
Contract Signature	Q3-2024

TB24 – IP Electrical Diesel Generators and buildings 59, 60



Scope:

Design, supply, installation, test and commissioning of the two (2) Investment Protection (IP) emergency electrical diesel generators (EDG) of 3.5MW each. The EDGs would be located in Building 59 and Building 60 respectively. Civil works for these buildings are also accounted for in the contract.



Estimated value / volume: <20M€

Estimated launch: Q4 2025

Procurement Process: Competitive Procedure with Negotiation

Contract Type: Design, supply, installation, test and commissioning

Key Dates:

Issue of Pre Information Notice	Q4-2024
Issue of Invitation to Participate (step 1)	Q1-2025
Issue of Call For Tender (step 2)	Q2-2025
Receipt of Tenders	Q1-2026
Contract Award	Q2-2026
Contract Signature	Q2-2026



Thank you for your attention

Follow us on:



www.f4e.europa.eu



www.twitter.com/fusionforenergy



www.youtube.com/fusionforenergy



www.linkedin.com/company/fusion-for-energy



www.flickr.com/photos/fusionforenergy

For further information please contact us at

industryportal-info@f4e.europa.eu

mentioning "Buildings" in subject of your email